

36705

Gravel has recently been placed on the Italian Garden paths in Lauriston Castle by the firm P1.

Please provide the:

specific specifications given/presented to P1

This work was requested as the paths were uneven. The work specification was to scrape back encroaching vegetation from edges of the paths, tooth the existing surface, import and spread 25mm depth of new gold self-binding surface compacted to levels. The area covered 465m<sup>2</sup>. The path material is a specific footpath gravel called CEDEC.

dates between which the work was carried out

This work was carried out between 7 and 11 February 2022.

quality assurance post work carried out

A follow up site inspection was carried out by a Parks and Greenspace Officer and remedial work was requested.

cost of work carried out separating between the cost of materials, labour and other costs.

The cost of the work was £8,165. It is not possible to provide an accurate breakdown of the cost but an approximate breakdown has been provided: 20% labour, 10% plant, 70% materials.